

TCEC ISO-Phase Bus Preventative Maintenance
RFP# 2026-202
Questions & Answers – Revised 4/30/26

1Q: Could the items below be made available - Drawing number U-12628 Sheet 1 of 4 for the STG?

1A: Yes, please see attached missing drawing.

2Q: The complete DUB Installation Manual, or at least all of the bolted flex connection details.

2A: See attached; IPB_InstructionManual.pdf (172 pages) is all we have in record.

3Q: NSB drawings for the option to add NSB inspection

3A: At this time, no drawings are available. Any determination of potential Non-Segregated Bus (NSB) work shall be made by the bidder and will require a site visit. A mandatory site visit is scheduled for May 14th. Please see details in the RFP.

3A – Revised – Drawings have been provided. Please see attached.

REVISION


0	26SEP06	kk
0		

All changes to be made on the CAD system.
No manual changes permitted on this drawing.

project:	3475
drn by:	kk
date:	26SEP06
scale:	NTS
chk'd:	
app'd:	

ABB POWER T & D
TREASURE COAST ENERGY
P.O. # PK00209

FOR SHOP USE ONLY
For Approval
(NOT FOR EXTERNAL USE)

<input type="checkbox"/> supercedes <input type="checkbox"/> supeceded by:		
 METAL ENCLOSED BUS SYSTEMS		
5kv 4000A 3P 3W INDOOR BUS DUCT CROSS SECTION		
3475-B002S	sh: 1	cont: -
		rev: 0

M012525-APDE076 S01 R0
 TREASURE COAST
 10/2/2006

Review does not relieve contractor from responsibility for errors or deviations from contract requirements


NO EXCEPTIONS NOTED
Release for manufacture

EXCEPTIONS NOTED
Release for manufacture
Revise and resubmit for distribution

RETURNED FOR CORRECTION
Do not proceed
Revise and resubmit for authorization

UTILITY ENGINEERING


[Signature]




Product code: 1540HC3TA1433M name plate: STD
 Rated Voltage: 5000 VOLTS
 BIL rating: 75 KV
 ONE MINUTE DRY WITHSTAND TEST LEVEL: 19 kv.
 Amperage: 4000 AMPERES CONTINUOUS
 Momentary: 78000 AMPERES (asym.) / 50322 AMPERES (sym.)
 Frequency: 60Hz
 Temp. rise: CONDUCTOR: 65°C } MAX. RISE @ RATED LOAD IN A 40°C AMBIENT
 HOUSING: 40°C }

Enclosure:	Outdoor: NON-VENTILATED - (BREATHERS ONLY) material: ALUMINUM finish: 2.5 MIL color: ANSI-61 weight: 112lbs/foot	Indoor: NON-VENTILATED - (BREATHERS ONLY) material: ALUMINUM finish: 1.5 MIL color: ANSI-61 weight: 112lbs/foot
Phase bars:	(2) - 0.63 X 6.00 BUS BAR(S) PER PHASE joint hdw: ST. STEEL material: COPPER - WITH SILVER CONTACTS	
Supports:	POLYESTER support spacing: 48 (min) 48 (max)	
Insulation:	phase bars/neutral: EPOXY INSULATION thickness: 0.09 TO 0.13 THK. shipping splits: INSULATING TAPES equipment terms: INSULATING TAPES	
Neutral bar:	NOT REQUIRED material: N/A rating: N/A	
Grounding:	CONTINUOUS GROUND BUS ground hdw: ST. STEEL (MOUNTED INTERNALLY) Size/matl: (1) - 0.25 X 2.00 BAR material: COPPER	
Heater sys:	NOT REQUIRED location: N/A element: N/A wiring: N/A conduit: N/A	
Control:	N/A	
Supply:	voltage: N/A source: N/A	
Add'l notes:	GENERAL NOTES: 1) FOR SHIP LOOSE LIST SEE DWG: (LATER) Crating Info	






LYT10.00
MICROFILMED:





PLAN VIEW



ELEVATION VIEW



- SHIP LOOSE KITS
- 025 INDR HSG SPLIT KIT (2) REQUIRED
 - 026 OTDR HSG KIT W/ HEATER (1) REQUIRED
 - 027 OTDR ELBOW KIT W/ HEATER (2) REQUIRED
 - 028 BUS BAR SPLIT KIT-3Ø (3) REQUIRED
 - 029 ELBOW BUS SPLIT KIT-3Ø (2) REQUIRED



Rated Voltage: 5000 VOLTS.
 BIL rating: 75KV
 ONE MINUTE DRY WITHSTAND TEST LEVEL: 19kv.
 Amperage: 4000 AMPERES CONTINUOUS
 Momentary: 78000 AMPERES (asym.) / 50322 AMPERES (sym.)
 Frequency: 50Hz
 Temp. rise: CONDUCTOR: 65°C } MAX. RISE @ RATED LOAD IN A 40°C AMBIENT
 HOUSING: 40°C }

Enclosure: Outdoor: NON-VENTILATED - (BREATHERS ONLY)
 material: STAINLESS STEEL
 finish: 2.5 MIL
 color: ANSI 61
 weight: 125lbs/foot
 Indoor: NON-VENTILATED - (BREATHERS ONLY)
 material: STAINLESS STEEL
 finish: 1.5 MIL
 color: ANSI 61
 weight: 125lbs/foot

Phase bars: (2) - 0.63X 6.00 BUS BAR(S) PER PHASE
 material: COPPER - WITH SILVER CONTACTS
 Supports: POLYESTER
 Insulation: phase bars/neutral: EPOXY INSULATION
 shipping splits: MOLDED INSULATING BOOTS
 equipment terms: MOLDED INSULATING BOOTS

Neutral bar: NOT REQUIRED
 material: N/A
 rating: N/A

Grounding: CONTINUOUS GROUND BUS (MOUNTED INTERNALLY)
 Size/mat: (1) - 0.25 X 2.00 BAR
 material: COPPER

Heater sys: REQUIRED - INDOOR AND OUTDOOR
 location: NON-HAZARDOUS AREA
 element: STANDARD ELEMENT (RATED 250W / 240V)
 WIRED TO OPERATE AT 120V/ 63W
 wiring: STRANDED COPPER W/600V SIS INSULATION
 conduit: BRAIDED METALLIC SHIELD
 Control: THERMOSTAT
 voltage: 120VAC (REQUIRES .52 AMP PER ELEMENT)
 source: INDOOR JUNCTION BOX FOR CUSTOMER'S 120V. SUPPLY

Add'l notes: GENERAL NOTES:
 1) FOR SHIP LOOSE LIST SEE DWG: 3475-A016

Field notes: INSTALLATION SHOULD NOT BE ATTEMPTED WITHOUT A THOROUGH UNDERSTANDING OF THE BUS DUCT DRAWINGS AND THE INSTALLATION INSTRUCTIONS. DO NOT TIGHTEN HOUSING AND BUS BAR JOINTS AT THE SHIPPING SPLITS UNTIL ALL THE EQUIPMENT TERMINATIONS ARE ALIGNED AND CONNECTED.

PLEASE CONSULT THE BUS DUCT INSTRUCTION MANUAL FOR HOUSING AND BUS BAR JOINT ASSEMBLY INSTRUCTIONS.

Supports: THE BUS DUCT SUPPORT LOCATIONS SHOWN MAY BE ADJUSTED TO ACCOMMODATE SITE VARIATIONS. IT IS RECOMMENDED THAT SUPPORTS BE SPACED APPROXIMATELY 12 TO 15 FEET CENTER-TO-CENTER ALONG STRAIGHT LENGTHS AND WITHIN 4 FEET OF ELBOWS, EQUIPMENT CONNECTIONS AND WALL FRAME ASSEMBLIES. CONSULT THE FACTORY FOR CONDITIONS BEYOND THESE RECOMMENDATIONS.

Dwg Units: ALL DIMENSIONS ARE IN INCHES, UNLESS OTHERWISE SPECIFIED.

Patent: BUS DUCT SHOWN ON THIS DRAWING IS PROTECTED UNDER U.S. PATENT #5053584.

- Legend:
- 001 SHIPPING I.D. NUMBER
 - H HEATER
 - NP NAME PLATE
 - SHIPPING SPLIT ASSEMBLY
 - T THERMOSTAT
 - G GROUND PAD
 - ACCESS COVER & BUS BAR JOINT LOCATION (FACTORY INSTALLED)
 - F FLANGE LOCATION
 - J JUNCTION BOX
 - SUGGESTED BUS DUCT SUPPORT LOCATION

MICROFILMED:




PROJECT: 3475	ABB POWER T & D TREASURE COAST ENERGY P.O. # PK00209	supersedes	is superseded by:
DATE: 26SEP06			
SCALE: NTS			
CERTIFIED	5KV 4000A 3P 3W BUS DUCT LAYOUT	3475-D001	sh: 1 cont: 3 rev: 3

REVISION	DATE	BY	DESCRIPTION
0	26SEP06	kk	
1	15NOV06	kk	REVISED PER CUSTOMER COMMENTS
2	18DEC06	kk	REVISED LOCATION OF SWGR



500 GRND TIE ASSY. DWG: 3475-D031 (1) REQUIRED

Review does not relieve contractor from responsibility for errors or deviations from contract requirements.

EXCEPTIONS NOTED
 Release for manufacture
 Revise and resubmit for distribution




- Notes:
- 1) ALL CONTACT SURFACES TO BE PLATED AS NOTED ON THE BUS DUCT LAYOUT.
 - 2) REFER TO THE BUS DUCT INSTRUCTION MANUAL FOR HARDWARE TORQUE VALUES, PROCEDURES AND INSULATING INSTRUCTIONS.
 - 3) REFER TO THE BUS DUCT LAYOUT DRAWING FOR PHASING ORDER.
 - 4) ALL DIMENSIONS ARE IN INCHES, UNLESS OTHERWISE SPECIFIED.
- Test Dept: TEST DEPT. TO CONFIRM DIMENSIONS MARKED: * PRIOR TO SHIPMENT.
- Reference: CUSTOMER DRAWING(S): ABB #901967 Rev.3




SWGR BUS: .75 x 4.00 COPPER BAR. INSULATED (2) BARS PER PHASE

REFER TO CROSS SECTION ON LAYOUT FOR GROUND BUS REQUIREMENT.
GROUND BUS REVERSAL



ELEVATION VIEW



SIDE VIEW

LTR	QTY	UOM	PART NUMBER	PART DESCRIPTION
H	3	EACH	3467-B090	MOLDED TERMINATION BOOT
G	9	EACH	256CEN	FILLER BUS
F	6	EACH	386CSN-D005	OFFSET ADAPTER BUS
E	6	EACH	386CSN-D005	OFFSET ADAPTER BUS
D	9	EACH	HFL5042T	1/2 x 4 1/2 HEX BOLT SET (S.S.)
C	12	EACH	HFL5022T	1/2 x 2 1/2 HEX BOLT SET (S.S.)
B	10	FEET	GSK1315	1/8 x 1 1/2 GASKET, EPDM w/PSA
A	22	EACH	HNL38103	3/8 HEX NUT SET (316S.S.)





MICROFILMED:		<input type="checkbox"/> supercedes <input type="checkbox"/> superseded by:	
project:	3475	ABB POWER T & D	TECHNIBUS METAL ENCLOSED BUS SYSTEMS
date:	25SEP06	TREASURE COAST ENERGY	
scale:	NTS	P.O. # PK00209	CERTIFIED
app'd:			
		5kV 4000A 3P 3W SWITCHGEAR TERMINATION	sh: 1 cont: 1 rev: 1

All changes to be made on the CAD system. No manual changes permitted on this drawing.




REVISION	DATE	BY	DESCRIPTION
0	25SEP06	kk	
1	06JAN07	kk	CERTIFIED PER CUSTOMER

Review does not relieve contractor from responsibility for errors or deviations from contract requirements.

NO EXCEPTIONS NOTED
Release for manufacture



XFMR FLANGE OPENING AND PROPOSED MOUNTING HOLE LOCATIONS



LT	QTY	UOM	PART NUMBER	PART DESCRIPTION
Z	1	EACH	X-120-0025-4/5	BOTTOM PANEL
Y	2	EACH	X-120-0026-4/2	SIDE PANELS
X	1	EACH	X-120-0023-4/17	REAR PANEL
W	1	EACH	3475-B051	FRONT PANEL
V	1	EACH	3475-B050	TOP COVER
U	76	EACH	CBF31113	5/16 x 1 1/4 CARR. BOLT SET (316 S.S.)
T	3	EACH	X-106-0003-2/39	MOLDED TERMINATION BOOT
S	1	EACH	709851-A080	MOLDED TERMINATION BOOT
R	1	EACH	3475-B091	MOLDED TERMINATION BOOT RH
Q	1	EACH	3475-B090	MOLDED TERMINATION BOOT
P	6	EACH	636CEN	ADAPTER BUS
N	17	EACH	256CEN	FILLER BUS
M	1	EACH	636CSI-B080/M	ADAPTER BUS
L	1	EACH	636CSI-B080/L	ADAPTER BUS
K	1	EACH	636CSI	OFFSET ADAPTER BUS
J	1	EACH	636CSI	OFFSET ADAPTER BUS
H	1	EACH	636CSI	OFFSET ADAPTER BUS
G	1	EACH	636CSI	OFFSET ADAPTER BUS
F	18	EACH	TYPE 2	4000A FLEX CONNECTOR KIT (6 PER PHASE)
E	12	EACH	HFL5023T	1/2 x 2 3/4 HEX. BOLT SET (S.S.)
D	36	EACH	HFL5041T	1/2 x 4 1/4 HEX. BOLT SET (S.S.)
C	30	EACH	HFL5033T	1/2 x 3 3/4 HEX. BOLT SET (S.S.)
B	58	FEET	GSK1315	1/8 x 1 1/2 GASKET, EPDM w/PSA
A	20	EACH	HFL5011T	1/2 x 1 1/4 HEX. BOLT SET (316 S.S.)

MICROFILMED:

project: 3475
 dn by: kk
 date: 25SEP06
 scale: NTS
 chk'd:
 app'd:

ABB POWER T & D
 TREASURE COAST ENERGY
 P.O. # PK00209

CERTIFIED

5kV 4000A 3P 3W
 TRANSFORMER TERMINATION
 3475-D006

sh: 1 cont: 1 rev: 1

REVISION

0	25SEP06	kk	kk
0	06JAN07	kk	kk

CERTIFIED PER CUSTOMER

Review does not relieve contractor from responsibility for errors or deviations from contract requirements.

NO EXCEPTIONS NOTED
 Release for manufacture

TECHNIBUS

1501 RAFF RD. S.W.
CANTON, OH 44708

TELEPHONE: (330) 478-6395

FAX: (330) 478-8377

TITLE: BUS DUCT INSPECTION REPORT

PAGE 1 OF 1

CUSTOMER NAME ABB Power Z&D DATE 2/28/07

PROJECT NUMBER 3475 UNIT UNDER TEST 1 RUN A

INSPECTED BY CD SPECIAL COMMENTS SS thru built

REFERENCE DRAWINGS D001/D005

VOLTAGE 5KV ASM #'S ON EACH END WARNING LABELS NAMEPLATE
AMPERAGE 4000

CONSTRUCTION:

OUTDOOR ASM INDOOR ASM - IF INDOOR, VENTILATED NON-VENTILATED
 HORIZONTAL VERTICAL UPPER VERTICAL ASM HAS REQUIRED
 VERTICAL LOWER ANGLES OR CHANNELS INSTALLED

WEATHER SEALS GASKETING CONFIG. ENCL. DIM. H 21 3/8 W 36.0 L 71 3/8
 EXTRUSION HOLES PLUGGED?
 TERMINATION TYPE SWGR. ATT. BOX DIM. H — W — L —

BUS SUPT. LOCATION MAX. ALLOWED VAPOR BARRIER
 BUS BRACED FOR VERT. INSTALLATION NOMINAL 48 (LOCATION, CAULKING OK)

ACCESS COVER LOC. FLANGE FLANGE ADAPTER CORRECT HOLE PATTERN
@ TERMINATION

EXTERNAL ENCLOSURE HARDWARE INTERNAL ENCLOSURE HARDWARE

BUS POSITION: ALUMINUM BUS COPPER BUS
 @ SHIPPING SPLITS @ TERMINATIONS CENTERLINE PHASE TO PHASE
 BUS DRILLING BUS PLATING TYPE: silver BUS INSULATION
 BUS JOINT TORQUES AND INSULATION HARDWARE, TYPE —

GROUND PAD: YES NO, IF YES INTERNAL EXTERNAL
GROUND BUS: YES NO, IF YES LOCATION DRILLING HARDWARE
 BUS PHASING IS CORRECT INSIDE ASSEMBLY BUS PHASING IS CORRECT TERM TO TERM

CLEARANCES: STRIKE -- PHASE TO PHASE PHASE TO GROUND
CREEP -- PHASE TO PHASE PHASE TO GROUND

HEATER SYSTEM: YES NOT APPLICABLE
 HEATER SPECIAL CONDITIONS: —
 LOCATION, ATTACHMENT AND CONNECTIONS EXTENSION LENGTH AND LUG TYPE
 TERMINAL BLOCK LOC. THERMOSTAT LOC. JUNCTION BOX LOC. AND TYPE —

APPEARANCE: CLEAN PAINT CURED EXT. PAINT FINISH ANSI 61 HOT PAINT
 SPECIAL ATTACHMENTS: —

PACKAGING:
SHIPPING BRACE REQUIRED YES NO

ASSEMBLED BY:
CLOCK # 1732
CLOCK #

Review does not relieve contractor from responsibility for errors or deviations from contract requirements.
NO EXCEPTIONS NOTED
Release for manufacture

TECHNIBUS

1501 RAFF RD. S.W.
CANTON, OH 44708

TITLE: BUS DUCT INSPECTION REPORT

TELEPHONE: (330) 478-6395

FAX: (330) 478-8377

PAGE 1 OF 1

CUSTOMER NAME ABB Power Ltd DATE 3/2/07

PROJECT NUMBER 3475 UNIT UNDER TEST 2 RUN B

INSPECTED BY ED SPECIAL COMMENTS _____

REFERENCE DRAWINGS D001/D005

VOLTAGE 5KV ASM #'S ON EACH END WARNING LABELS NAMEPLATE
AMPERAGE 4000

CONSTRUCTION:

OUTDOOR ASM INDOOR ASM - IF INDOOR, VENTILATED NON-VENTILATED
 HORIZONTAL VERTICAL UPPER VERTICAL ASM HAS REQUIRED
 VERTICAL LOWER ANGLES OR CHANNELS INSTALLED

WEATHER SEALS GASKETING CONFIG. ENCL. DIM. H 21 3/8 W 36.0 L 7 1/2

EXTRUSION HOLES PLUGGED?
 TERMINATION TYPE SWGR. ATT. BOX DIM. H - W - L -

BUS SUPT. LOCATION MAX. ALLOWED VAPOR BARRIER
 BUS BRACED FOR VERT. INSTALLATION NOMINAL 48 (LOCATION, CAULKING OK)

ACCESS COVER LOC. FLANGE FLANGE ADAPTER CORRECT HOLE PATTERN
@ TERMINATION

EXTERNAL ENCLOSURE HARDWARE INTERNAL ENCLOSURE HARDWARE

BUS POSITION:

ALUMINUM BUS COPPER BUS
 @ SHIPPING SPLITS @ TERMINATIONS CENTERLINE PHASE TO PHASE
 BUS DRILLING BUS PLATING TYPE: Silver BUS INSULATION
 BUS JOINT TORQUES AND INSULATION HARDWARE, TYPE _____

GROUND PAD: YES NO, IF YES INTERNAL EXTERNAL
GROUND BUS: YES NO, IF YES LOCATION DRILLING HARDWARE
 BUS PHASING IS CORRECT INSIDE ASSEMBLY BUS PHASING IS CORRECT TERM TO TERM

CLEARANCES: STRIKE -- PHASE TO PHASE PHASE TO GROUND
CREEP -- PHASE TO PHASE PHASE TO GROUND

HEATER SYSTEM: YES NOT APPLICABLE

HEATER SPECIAL CONDITIONS:
 LOCATION, ATTACHMENT AND CONNECTIONS EXTENSION LENGTH AND LUG TYPE
 TERMINAL BLOCK LOC. THERMOSTAT LOC. JUNCTION BOX LOC. AND TYPE _____

APPEARANCE: CLEAN PAINT CURED EXT. PAINT FINISH ANSI 60 INT. PAINT
 SPECIAL ATTACHMENTS: _____

PACKAGING:

SHIPPING BRACE REQUIRED YES NO

ASSEMBLED BY:

CLOCK # 1355

CLOCK # 1819

TECHNIBUS

1501 RAFF RD. S.W.
CANTON, OH 44708

TELEPHONE: (330) 478-6395
FAX: (330) 478-8377
PAGE 1 OF 1

TITLE: BUS DUCT INSPECTION REPORT

CUSTOMER NAME ABB Power T&D DATE 3/1/07
PROJECT NUMBER 3475 UNIT UNDER TEST 11 RUN A
INSPECTED BY MAC SPECIAL COMMENTS 316 SS COVER SCREWS (THRU BOCT)
REFERENCE DRAWINGS D001

VOLTAGE 5,000 ASM #'S ON EACH END WARNING LABELS NAMEPLATE
AMPERAGE 4,000

CONSTRUCTION:

OUTDOOR ASM INDOOR ASM - IF INDOOR, VENTILATED NON-VENTILATED
 HORIZONTAL VERTICAL UPPER VERTICAL ASM HAS REQUIRED
ELBOW VERTICAL LOWER ANGLES OR CHANNELS INSTALLED

WEATHER SEALS GASKETING CONFIG. ENCL. DIM. H 14" W 27" L B=29 5/8" A=64 1/8"
 EXTRUSION HOLES PLUGGED?
 TERMINATION TYPE — ATT. BOX DIM. H — W — L —

BUS SUPT. LOCATION MAX. ALLOWED VAPOR BARRIER GLASTIC 1/2 HR
 BUS BRACED FOR VERT. INSTALLATION NOMINAL 48" (LOCATION, CAULKING OK)

ACCESS COVER LOC. FLANGE FLANGE ADAPTER CORRECT HOLE PATTERN @ TERMINATION

EXTERNAL ENCLOSURE HARDWARE INTERNAL ENCLOSURE HARDWARE

BUS POSITION:

ALUMINUM BUS COPPER BUS
 @ SHIPPING SPLITS @ TERMINATIONS CENTERLINE PHASE TO PHASE
 BUS DRILLING BUS PLATING TYPE: SILVER BUS INSULATION
 BUS JOINT TORQUES AND INSULATION HARDWARE, TYPE —

GROUND PAD: YES NO, IF YES INTERNAL EXTERNAL
GROUND BUS: YES NO, IF YES LOCATION DRILLING HARDWARE
 BUS PHASING IS CORRECT INSIDE ASSEMBLY BUS PHASING IS CORRECT TERM TO TERM

CLEARANCES: STRIKE -- PHASE TO PHASE PHASE TO GROUND
CREEP -- PHASE TO PHASE PHASE TO GROUND

HEATER SYSTEM:

YES NOT APPLICABLE
 HEATER SPECIAL CONDITIONS:
 LOCATION, ATTACHMENT AND CONNECTIONS EXTENSION LENGTH AND LUG TYPE
 TERMINAL BLOCK LOC. THERMOSTAT LOC. JUNCTION BOX LOC. AND TYPE OUT/IN

APPEARANCE:

CLEAN PAINT CURED EXT. PAINT FINISH AISI 61 INT. PAINT
 SPECIAL ATTACHMENTS: —

PACKAGING:

SHIPPING BRACE REQUIRED YES NO

ASSEMBLED BY:
CLOCK # 1790
CLOCK #

TECHNIBUS

1501 RAFF RD. S.W.
CANTON, OH 44708

TELEPHONE: (330) 478-6395
FAX: (330) 478-8377

TITLE: BUS DUCT INSPECTION REPORT

PAGE 1 OF 1

CUSTOMER NAME ABB Power T & D DATE 3/5/07
PROJECT NUMBER 3475 UNIT UNDER TEST 12 RUN A
INSPECTED BY MAC SPECIAL COMMENTS 316SS COVER THRU BOLTS / SS HOUSING
REFERENCE DRAWINGS D001

VOLTAGE 5,000 ASM #'S ON EACH END WARNING LABELS NAMEPLATE
AMPERAGE 4,000

CONSTRUCTION:

OUTDOOR ASM INDOOR ASM - IF INDOOR, VENTILATED NON-VENTILATED
 HORIZONTAL VERTICAL UPPER VERTICAL ASM HAS REQUIRED
ELBOW VERTICAL LOWER ANGLES OR CHANNELS INSTALLED
 WEATHER SEALS GASKETING CONFIG. ENCL. DIM. H 18" W 36" L 119" CENTER
 EXTRUSION HOLES PLUGGED? ATT. BOX DIM. H — W — L — TO CENTER
 TERMINATION TYPE —

BUS SUPT. LOCATION MAX. ALLOWED, VAPOR BARRIER
 BUS BRACED FOR VERT. INSTALLATION NOMINAL 4/8" (LOCATION, CAULKING OK)
 ACCESS COVER LOC. FLANGE FLANGE ADAPTER CORRECT HOLE PATTERN
@ TERMINATION

EXTERNAL ENCLOSURE HARDWARE INTERNAL ENCLOSURE HARDWARE

BUS POSITION:

ALUMINUM BUS COPPER BUS
 @ SHIPPING SPLITS @ TERMINATIONS CENTERLINE PHASE TO PHASE
 BUS DRILLING BUS PLATING TYPE: SILVER BUS INSULATION
 BUS JOINT TORQUES AND INSULATION HARDWARE, TYPE —

GROUND PAD: YES NO, IF YES INTERNAL EXTERNAL
GROUND BUS: YES NO, IF YES LOCATION DRILLING HARDWARE
 BUS PHASING IS CORRECT INSIDE ASSEMBLY BUS PHASING IS CORRECT TERM TO TERM

CLEARANCES: STRIKE -- PHASE TO PHASE PHASE TO GROUND
CREEP -- PHASE TO PHASE PHASE TO GROUND

HEATER SYSTEM:

YES NOT APPLICABLE
 HEATER SPECIAL CONDITIONS: —
 LOCATION, ATTACHMENT AND CONNECTIONS EXTENSION LENGTH AND LUG TYPE
 TERMINAL BLOCK LOC. THERMOSTAT LOC. JUNCTION BOX LOC. AND TYPE —

APPEARANCE: CLEAN PAINT CURED EXT. PAINT FINISH ANSI 61 INT. PAINT
 SPECIAL ATTACHMENTS: —

PACKAGING:

SHIPPING BRACE REQUIRED YES NO

ASSEMBLED BY:
CLOCK # 1814
CLOCK #

TECHNIBUS

1501 RAFF RD. S.W.
CANTON, OH 44708

TELEPHONE: (330) 478-6395

FAX: (330) 478-8377

TITLE: BUS DUCT INSPECTION REPORT

PAGE 1 OF 1

CUSTOMER NAME ABB Power T&D DATE 3/3/07

PROJECT NUMBER 3475 #2 UNIT UNDER TEST 13 RUN A

INSPECTED BY MAC SPECIAL COMMENTS SS THRU BOLTS + BUS HDWR

REFERENCE DRAWINGS D001, D006

VOLTAGE 5,000 ASM #'S ON EACH END WARNING LABELS NAMEPLATE
AMPERAGE 4,000

CONSTRUCTION:

OUTDOOR ASM INDOOR ASM - IF INDOOR, VENTILATED NON-VENTILATED
 HORIZONTAL VERTICAL UPPER VERTICAL ASM HAS REQUIRED
 VERTICAL LOWER ANGLES OR CHANNELS INSTALLED

WEATHER SEALS GASKETING CONFIG. ENCL. DIM. H 41 7/8" W 36" LB = 78 1/4"
 EXTRUSION HOLES PLUGGED? A = 112 5/8"
 TERMINATION TYPE XFM12 ATT. BOX DIM. H - W - L

BUS SUPT. LOCATION MAX. ALLOWED VAPOR BARRIER 2 HR FIRESTOP
 BUS BRACED FOR VERT. INSTALLATION NOMINAL 48" (LOCATION, CAULKING OK)

ACCESS COVER LOC. FLANGE FLANGE ADAPTER CORRECT HOLE PATTERN
@ TERMINATION

EXTERNAL ENCLOSURE HARDWARE INTERNAL ENCLOSURE HARDWARE

BUS POSITION: ALUMINUM BUS COPPER BUS
 @ SHIPPING SPLITS @ TERMINATIONS CENTERLINE PHASE TO PHASE
 BUS DRILLING BUS PLATING TYPE: SILVER BUS INSULATION
 BUS JOINT TORQUES AND INSULATION HARDWARE, TYPE

GROUND PAD: YES NO, IF YES INTERNAL EXTERNAL
GROUND BUS: YES NO, IF YES LOCATION DRILLING HARDWARE
 BUS PHASING IS CORRECT INSIDE ASSEMBLY BUS PHASING IS CORRECT TERM TO TERM

CLEARANCES: STRIKE -- PHASE TO PHASE PHASE TO GROUND
CREEP -- PHASE TO PHASE PHASE TO GROUND

HEATER SYSTEM: YES NOT APPLICABLE
 HEATER SPECIAL CONDITIONS:

LOCATION ATTACHMENT AND CONNECTIONS EXTENSION LENGTH AND LUG TYPE
 TERMINAL BLOCK LOC. THERMOSTAT LOC. JUNCTION BOX LOC. AND TYPE

APPEARANCE: CLEAN PAINT CURED EXT. PAINT FINISH ANSI 61 INT. PAINT
 SPECIAL ATTACHMENTS:

PACKAGING:
SHIPPING BRACE REQUIRED YES NO

ASSEMBLED BY:
CLOCK # 1801
CLOCK #

TECHNIBUS

1501 RAFF RD. S.W.
CANTON, OH 44708

TELEPHONE: (330) 478-6395
FAX: (330) 478-8377

TITLE: BUS DUCT INSPECTION REPORT

PAGE 1 OF 1

CUSTOMER NAME ABB POWER T&D DATE 3/3/07

PROJECT NUMBER 3475 UNIT UNDER TEST 15 RUN B

INSPECTED BY MAC SPECIAL COMMENTS _____

REFERENCE DRAWINGS _____

VOLTAGE 5KV ASM #'S ON EACH END WARNING LABELS NAMEPLATE
AMPERAGE 4,000

CONSTRUCTION:

OUTDOOR ASM INDOOR ASM - IF INDOOR, VENTILATED NON-VENTILATED
 HORIZONTAL VERTICAL UPPER VERTICAL ASM HAS REQUIRED
 VERTICAL LOWER ANGLES OR CHANNELS INSTALLED

WEATHER SEALS GASKETING CONFIG. [] ENCL. DIM. H/4.0 W 36.0 L 55 3/4
 EXTRUSION HOLES PLUGGED?
 TERMINATION TYPE _____ ATT. BOX DIM. H _____ W _____ L _____

BUS SUPT. LOCATION MAX. ALLOWED VAPOR BARRIER
 BUS BRACED FOR VERT. INSTALLATION NOMINAL 48 (LOCATION, CAULKING OK)
 ACCESS COVER LOC. FLANGE FLANGE ADAPTER CORRECT HOLE PATTERN
@ TERMINATION

EXTERNAL ENCLOSURE HARDWARE INTERNAL ENCLOSURE HARDWARE

BUS POSITION:

ALUMINUM BUS COPPER BUS
 @ SHIPPING SPLITS @ TERMINATIONS CENTERLINE PHASE TO PHASE
 BUS DRILLING BUS PLATING TYPE: silver BUS INSULATION
 BUS JOINT TORQUES AND INSULATION HARDWARE, TYPE _____

GROUND PAD: YES NO, IF YES INTERNAL EXTERNAL
GROUND BUS: YES NO, IF YES LOCATION DRILLING HARDWARE
 BUS PHASING IS CORRECT INSIDE ASSEMBLY BUS PHASING IS CORRECT TERM TO TERM

CLEARANCES: STRIKE -- PHASE TO PHASE PHASE TO GROUND
CREEP -- PHASE TO PHASE PHASE TO GROUND

HEATER SYSTEM:

YES NOT APPLICABLE
 HEATER SPECIAL CONDITIONS: _____
 LOCATION, ATTACHMENT AND CONNECTIONS EXTENSION LENGTH AND LUG TYPE
 TERMINAL BLOCK LOC. THERMOSTAT LOC. JUNCTION BOX LOC. AND TYPE Indoor

APPEARANCE:

CLEAN PAINT CURED EXT. PAINT FINISH ANSI 61 INT. PAINT
 SPECIAL ATTACHMENTS: _____

PACKAGING:

SHIPPING BRACE REQUIRED YES NO

ASSEMBLED BY:
CLOCK # 1790
CLOCK # _____

TECHNIBUS

1501 RAFF RD. S.W.
CANTON, OH 44708

TELEPHONE: (330) 478-6395
FAX: (330) 478-8377

TITLE: BUS DUCT INSPECTION REPORT

PAGE 1 OF 1

CUSTOMER NAME ABB Power T+D DATE 3/6/07
PROJECT NUMBER 3475 UNIT UNDER TEST 16 RUN B
INSPECTED BY MAC SPECIAL COMMENTS 316 SS THRU BOLTS COVER
REFERENCE DRAWINGS D001, D006

VOLTAGE 5KV ASM #'S ON EACH END WARNING LABELS NAMEPLATE
AMPERAGE 4000

CONSTRUCTION:

OUTDOOR ASM INDOOR ASM - IF INDOOR, VENTILATED NON-VENTILATED
 HORIZONTAL VERTICAL UPPER VERTICAL ASM HAS REQUIRED
 VERTICAL LOWER ANGLES OR CHANNELS INSTALLED

WEATHER SEALS GASKETING CONFIG. ENCL. DIM. H 42" W 36" L 88 1/4"
 EXTRUSION HOLES PLUGGED?
 TERMINATION TYPE X FMR ATT. BOX DIM. H - W - L

BUS SUPT. LOCATION MAX. ALLOWED, VAPOR BARRIER 2 HR FIRE STOP
 BUS BRACED FOR VERT. INSTALLATION NOMINAL 48" (LOCATION, CAULKING OK) FRAM
 ACCESS COVER LOC. FLANGE FLANGE ADAPTER CORRECT HOLE PATTERN
@ TERMINATION

EXTERNAL ENCLOSURE HARDWARE INTERNAL ENCLOSURE HARDWARE

BUS POSITION:

ALUMINUM BUS COPPER BUS
 @ SHIPPING SPLITS @ TERMINATIONS CENTERLINE PHASE TO PHASE
 BUS DRILLING BUS PLATING TYPE: SILVER [] BUS INSULATION
 BUS JOINT TORQUES AND INSULATION HARDWARE, TYPE STAINLESS

GROUND PAD: YES NO, IF YES INTERNAL EXTERNAL
GROUND BUS: YES NO, IF YES LOCATION DRILLING [] HARDWARE
 BUS PHASING IS CORRECT INSIDE ASSEMBLY [] BUS PHASING IS CORRECT TERM TO TERM

CLEARANCES: STRIKE -- PHASE TO PHASE PHASE TO GROUND
CREEP -- PHASE TO PHASE PHASE TO GROUND

HEATER SYSTEM: YES NOT APPLICABLE
 HEATER SPECIAL CONDITIONS: -

LOCATION, ATTACHMENT AND CONNECTIONS EXTENSION LENGTH AND LUG TYPE
 TERMINAL BLOCK LOC. THERMOSTAT LOC. JUNCTION BOX LOC. AND TYPE -

APPEARANCE: CLEAN PAINT CURED EXT. PAINT FINISH ANSI 61 INT. PAINT
 SPECIAL ATTACHMENTS: -

PACKAGING:
SHIPPING BRACE REQUIRED YES NO

ASSEMBLED BY:
CLOCK # 1771
CLOCK # _____

TECHNIBUS
1501 Raff Rd. S.W.
Canton, Ohio 44708

Telephone (330) 478-6395
Fax: (330) 478-8377

Title: **Bus Duct Dielectric Test**
POWER FREQUENCY WITHSTAND - HIPOT
(ANSI C37.23-2003 -5.2.3, TABLE 1, 2, 3, 4)

JOB #: T3475 CUSTOMER: ABB DATE: 3-6-07
PROJECT: Treasure Coast Energy Center VOLTAGE: 5K
HIPOT MAKE: Hospital HIPOT S/N: 2004 LAST CAL DATE: 12-7-06
RELATIVE HUMIDITY: 28% BAROMETRIC PRESSURE: 743 mm HG
TEMPERATURE WET BULB: 7 Degrees C TEMPERATURE DRY BULB: 16 Degrees C

ALL PHASES NOT BEING TESTED ARE GROUNDED DURING TEST.	TEST VOLTAGE (kv 1 min.) / LEAKAGE CURRENT (ma)**						
	Φ 1-G	Φ 2-G	Φ 3-G	Φ 4-G	Φ 5-G	Φ 6-G	WIRES
skid three run A arm 013	19 KV	19 KV	19 KV	— KV	— KV	— KV	1.5 KV
	1.8 ma	1.8 ma	1.8 ma	— ma	— ma	— ma	1.2 ma
skid four run B arm 016	19 KV	19 KV	19 KV	— KV	— KV	— KV	1.5 KV
	1.8 ma	1.8 ma	1.8 ma	— ma	— ma	— ma	1.1 ma
—	— KV	— KV	— KV	— KV	— KV	— KV	— KV
—	— ma	— ma	— ma	— ma	— ma	— ma	— ma

** CURRENT READING MAY NOT ALWAYS REFLECT LEAKAGE OF AN INDIVIDUAL ASSEMBLY. MULTIPLE ASSEMBLIES MAY BE TESTED AT ONCE.

TESTED BY: Ronald Nadeau CUSTOMER WITNESS: Y/N
LOCATION IN SHOP: bus duct test area ACCEPTED: Y/N
CUSTOMER SIGNATURE: _____

CONTROL WIRING INSULATION DIELECTRIC TEST
DISCONNECT ALL CIRCUIT GROUNDS AND ANY ELECTRONIC OR OTHER CIRCUIT COMPONENTS THAT MAY BE DAMAGED.
CHECKING TO BE SURE THAT THE CIRCUITS ARE NOT GROUNDED WITH AN OHMMETER, PROCEED TO CLEAR ANY GROUNDS FOUND WITH THIS CHECK.
THIS MUST BE CHECKED POINT TO POINT UNTIL ALL CIRCUITS CHECKED.
 APPLY 1500 VOLTS A.C. 60HZ FROM CONTROL WIRING TO GROUND FOR ONE MINUTE.
 APPLY 1800 VOLTS A.C. 60HZ ON EACH WIRE FOR ONE SECOND UNTIL ALL WIRES AND TERMINALS HAVE BEEN TESTED.

COMMENTS: star 304 ss key

PASSED Ronald Nadeau
TESTER SIGNATURE

Form 10 02-28 Revision #7 (4/2/05)

Review does not relieve contractor from responsibility for errors or deviations from contract requirements.

NO EXCEPTIONS NOTED
Release for manufacture

TECHNIBUS
1501 Raff Rd. S.W.
Canton, Ohio 44708

Telephone (330) 478-6395
Fax: (330) 478-8377

Title: **Bus Duct Dielectric Test**
POWER FREQUENCY WITHSTAND - HIPOT
(ANSI C37.23 -2003 -5.2.3, TABLE 1, 2, 3, 4)

JOB #: T3475 CUSTOMER: ABB DATE: 3-6-07
PROJECT: Tennessee Coast Energy Center RATING: 5K
HIPOT MAKE: Hipotronics HIPOT S/N: 20A LAST CAL. DATE: 12-7-06
RELATIVE HUMIDITY: 28 % BAROMETRIC PRESSURE: 743 mm HG
TEMPERATURE WET BULB: 7 Degrees C TEMPERATURE DRY BULB: 16 Degrees C

ALL PHASES NOT BEING TESTED ARE GROUNDED DURING TEST.	TEST VOLTAGE (kv 1 min.) / LEAKAGE CURRENT (ma) **						
	Φ 1-G	Φ 2-G	Φ 3-G	Φ 4-G	Φ 5-G	Φ 6-G	WIRES
<u>skid three</u> <u>run A</u> <u>asm 011</u>	<u>19</u> KV	<u>19</u> KV	<u>19</u> KV	<u>-</u> KV	<u>-</u> KV	<u>-</u> KV	<u>1.5</u> KV
	<u>1.1</u> ma	<u>1.0</u> ma	<u>0.9</u> ma	<u>-</u> ma	<u>-</u> ma	<u>-</u> ma	<u>0.6</u> ma

<u>skid three</u> <u>run A</u> <u>asm 012</u>	<u>19</u> KV	<u>19</u> KV	<u>19</u> KV	<u>-</u> KV	<u>-</u> KV	<u>-</u> KV	<u>1.5</u> KV
	<u>1.6</u> ma	<u>1.6</u> ma	<u>1.6</u> ma	<u>-</u> ma	<u>-</u> ma	<u>-</u> ma	<u>0.5</u> ma

<u>skid four</u> <u>run B</u> <u>asm 015</u>	<u>19</u> KV	<u>19</u> KV	<u>19</u> KV	<u>-</u> KV	<u>-</u> KV	<u>-</u> KV	<u>1.5</u> KV
	<u>1.0</u> ma	<u>1.0</u> ma	<u>1.0</u> ma	<u>-</u> ma	<u>-</u> ma	<u>-</u> ma	<u>0.6</u> ma

** CURRENT READING MAY NOT ALWAYS REFLECT LEAKAGE OF AN INDIVIDUAL ASSEMBLY. MULTIPLE ASSEMBLIES MAY BE TESTED AT ONCE.

TESTED BY: Ronald Nadeau CUSTOMER WITNESS: Y/N
LOCATION IN SHOP: bus duct test area ACCEPTED: Y/N
CUSTOMER SIGNATURE: _____

CONTROL WIRING INSULATION DIELECTRIC TEST

DISCONNECT ALL CIRCUIT GROUNDS AND ANY ELECTRONIC OR OTHER CIRCUIT COMPONENTS THAT MAY BE DAMAGED.
CHECKING TO BE SURE THAT THE CIRCUITS ARE NOT GROUNDED WITH AN OHMMETER, PROCEED TO CLEAR ANY GROUNDS FOUND WITH THIS CHECK.
THIS MUST BE CHECKED POINT TO POINT UNTIL ALL CIRCUITS CHECKED.

- APPLY 1500 VOLTS A.C. 60HZ FROM CONTROL WIRING TO GROUND FOR ONE MINUTE.
- APPLY 1000 VOLTS A.C. 60HZ ON EACH WIRE FOR ONE SECOND UNTIL ALL WIRES AND TERMINALS HAVE BEEN TESTED.

COMMENTS: oktr 304 is ok

PASSED _____
TESTER SIGNATURE

TECHNIBUS
1501 Raff Rd. S.W.
Canton, Ohio 44708

Telephone (330) 478-6395
Fax: (330) 478-8377

Title: **Bus Duct Dielectric Test**
POWER FREQUENCY WITHSTAND - HIPOT
(ANSI C37.23 -2003 -5.2.3, TABLE 1, 2, 3, 4)

JOB #: T3475 CUSTOMER: ABB DATE: 3-3-07
PROJECT: Treasure Coast Energy Center V. RATING: 5K
HIPOT MAKE: Hypotronics HIPOT S/N: 20A LAST CAL. DATE: 12-7-06
RELATIVE HUMIDITY: 28 % BAROMETRIC PRESSURE: 725 mm HG
TEMPERATURE WET BULB: 8 Degrees C TEMPERATURE DRY BULB: 17 Degrees C

ALL PHASES NOT BEING TESTED ARE GROUNDED DURING TEST. ASSY'S	TEST VOLTAGE (kv 1 min.) / LEAKAGE CURRENT (ma) **						
	Φ 1-G	Φ 2-G	Φ 3-G	Φ 4-G	Φ 5-G	Φ 6-G	WIRES
<u>skid one</u>	19 KV	19 KV	19 KV	- KV	- KV	- KV	- KV
<u>run A</u>	1.2 ma	1.2 ma	1.2 ma	- ma	- ma	- ma	- ma
<u>asm 001</u>							
<u>skid two</u>	19 KV	19 KV	19 KV	- KV	- KV	- KV	- KV
<u>run B</u>	1.2 ma	1.2 ma	1.2 ma	- ma	- ma	- ma	- ma
<u>asm 002</u>							
	- KV	- KV	- KV	- KV	- KV	- KV	- KV
	- ma	- ma	- ma	- ma	- ma	- ma	- ma

** CURRENT READING MAY NOT ALWAYS REFLECT LEAKAGE OF AN INDIVIDUAL ASSEMBLY. MULTIPLE ASSEMBLIES MAY BE TESTED AT ONCE.

TESTED BY: Ronald H. Nadeau CUSTOMER WITNESS: N
LOCATION IN SHOP: bus duct test area ACCEPTED: ✓ CUSTOMER SIGNATURE: _____

CONTROL WIRING INSULATION DIELECTRIC TEST
DISCONNECT ALL CIRCUIT GROUNDS AND ANY ELECTRONIC OR OTHER CIRCUIT COMPONENTS THAT MAY BE DAMAGED CHECKING TO BE SURE THAT THE CIRCUITS ARE NOT GROUNDED WITH AN OHMMETER, PROCEED TO CLEAR ANY GROUNDS FOUND WITH THIS CHECK. THIS MUST BE CHECKED POINT TO POINT UNTIL ALL CIRCUITS CHECKED.
[] APPLY 1500 VOLTS A.C. 60HZ FROM CONTROL WIRING TO GROUND FOR ONE MINUTE.
[] APPLY 1500 VOLTS A.C. 60HZ ON EACH WIRE FOR ONE SECOND UNTIL ALL WIRES AND TERMINALS HAVE BEEN TESTED.


COMMENTS: indr alum bray

PASSED Ronald J. Nadeau
TESTER SIGNATURE

Form 10.02-28 Revision #7 (4/12/05)

Review does not relieve contractor from responsibility for errors or deviations from contract requirements.
NO EXCEPTIONS NOTED
Release for manufacture

Technibus™



Instruction Manual

TECHNIBUS

Metal Enclosed Bus Systems

Review does not relieve contractor from responsibility for errors or deviations from contract requirements.

NO EXCEPTIONS NOTED
Release for manufacture

Table of Contents

Introduction	
Installation Drawings	4
Product Description	
Ratings	5
Conductors	5
Conductor Joints	5
Insulation	5
Bus Support Insulators	5
Enclosure	5
Expansion	6
Grounding	6
Structural Supports	6
Receiving, Handling and Storage	
Shipping and Crating	7
Sample Crate Markings	7
Lifting	7
Long Term Indoor Storage	7
Temporary Outdoor Storage	7
Damages	7
Shortages	7
Ship Loose Bill of Material Examples	8
Equipment Handling Illustrations	9
Installation / Shipping Fixtures	
Drawings	10
Identification	10
Lifting Individual Assemblies	10
Shipping Fixtures	10
Contamination	10
Assembly	10
Modifications	10
Installation Illustrations	
Indoor Non-Vented Enclosure Assembly	11
Instructions	
Indoor Vented Enclosure Assembly Instructions	12
Outdoor Non-Vented Enclosure Assembly	13
Instructions	
Wall Entrance Assembly Instructions	14
Heater System Assembly - Standard	15
Heater System Assembly - Hazardous Area	16
Ground System Assembly Instructions	17
Hanger & Wall Brace Support Assembly	18
Instructions	

Table of Contents

Roof Support Style I Assembly Instructions	19
Roof Support Style II Assembly Instructions	20
Single Column Support Assembly Instructions	21
Double Column Support Assembly Instructions	22
Bus joint Assembly / Torque Requirements	
Alignment	23
Contact Surfaces	23
Typical Bus Joint	23
Copper Bus Joints	23
Aluminum Bus Joints	23
Boot Insulation	24
Bus Joint Assembly Illustration	24
Low Voltage Insulating Instructions	
600 volt and DC Insulating Instructions	25
Medium Voltage Insulating Instructions	
5kv and 15kv Insulating Instructions	26
Insulating Instructions for 25kv and 38kv	
Instructions	27
Stud Connector Taping	28
Flexible Connector Taping	28
25kv and 38kv Insulating Illustration	28
Test	
Bus Insulation	29
Control Wiring	29
Power Frequency Withstand	29
Test levels	29
Maintenance	
Operation	30
Maintenance	30
Recommendations	30
Spare Parts List	31

TECHNIBUS
Metal Enclosed Bus Systems

Introduction

Introduction

All aspects of installation, operation and maintenance of the Technibus™ Metal Enclosed Bus System must be thoroughly understood and performed under the supervision of qualified personnel.

Responsible personnel should establish procedures which insure the safety of personnel and equipment. Specific safety-related procedures are not covered by this manual. Please refer to all installation drawings, other equipment manufacturers' specifications, appropriate ANSI or NEMA requirements and your own company's safety rules.

Information contained in this manual is to be used in conjunction with installation drawings provided for each system. Installation drawings typically include the drawings listed below which establish ratings and identify specific project requirements - which may vary from standard product features described in this manual.

Installation Drawings

- Bus Duct Layout Plan and elevation views of duct routing. This drawing also lists and identifies all assemblies provided by the factory. Typical cross-sectional view of duct, providing ratings, housing size, weight per foot, material descriptions, and bus duct structural support locations.
- Equipment Terminations Details of the bus and enclosure connection to the equipment.
- Ship Loose Bill of Materials Lists and identifies all parts required for field assemblies.

Product Description

Ratings	Each Technibus system is designed to meet the voltage, amperage, and fault level requirements specified on the drawing(s) provided.
Conductors	Copper or aluminum is sized in accordance with the specified ratings to operate within ANSI C37.23 temperature rise limitations.
Conductor Joints	Contact surfaces are prepared and plated to satisfy the specific application. Refer to our equipment termination drawings and shipping split assembly illustrations for specific hardware requirements.
Insulation	Factory insulation is not required on 600 volt conductors. The 5-38 kV conductors are insulated with 130° C epoxy coating.
Bus Support Insulators	Technibus bus support insulators are furnished to suit the electrical and mechanical requirements specified for each installation. Molded glass polyester is standard for systems rated up to 15,000 volts. Porcelain is optional for 5 & 15 kV. Porcelain is standard for 34,000 volt systems.
Enclosure	<p>Painted, non-magnetic aluminum enclosures eliminate hysteresis losses. Due to its inherent high conductivity, it also minimizes induced I²R losses.</p> <p>Technibus's high conductivity aluminum enclosures also shield external steel members from undesirable magnetic heating.</p> <p><u>Outdoor installations</u></p> <ul style="list-style-type: none">• Top and sides are not ventilated• Screened breather/drains are provided along enclosure bottom to prevent accumulation of moisture• All exposed hardware is stainless steel• Gaskets are concealed to prevent deterioration• Electric space heaters are provided to prevent the formation of internal condensation <p><u>Indoor installations</u></p> <ul style="list-style-type: none">• Non-ventilated or ventilated enclosures may be provided as specified• All hardware is plated steel

Product Description

Expansion	Provisions for the bus and enclosure expansion are furnished as required by the configuration and lengths of each system.
Grounding	The entire length of the enclosure must be properly grounded. Mating surfaces of ground bonds are unpainted to assure continuity. External or internal pads are provided for connection to the station ground. When specified, a separate ground bus attaching to the equipment ground may be provided as an option.
Structural Supports	Our Indoor and Outdoor structures will be painted to match the enclosure. Refer to illustration drawings and the Bus Duct Layout drawing for the suggested support locations and source of supply.

Receiving, Handling, and Storage

Shipping and Crating

Standard crating is suited for shipment via common carrier, motor freight, and indoor storage. Crates may be marked to indicate special handling and/or storage procedures. Each crate will be marked with job number, customer purchase order number, special markings, shipping address, description, and weight (see diagram). A ship loose bill of materials will be supplied with each job that will show all assemblies, assembly kits, and accessories. Ship Loose Bill of Material examples are shown on page 8

Sample Crate Markings

TECHNIBUS	
Metal Enclosed Bus Systems	
Job No.	_____
P.O. No.	_____
Ship To:	_____
Description:	_____
Weight:	_____

Lifting

Sling the bus package with lifting slings and a spreader bar so the weight is distributed equally as shown on page 9.

Caution Caution Caution Caution Caution
Do not stack any of the shipping crates as damage may occur.

Long Term Indoor Storage

The storage area must be clean and dry to prevent condensation and corrosion. **Note: Equipment should be subjected to a power frequency withstand test (see test section) prior to storage exceeding three (3) months.**

Temporary Outdoor Storage

Place timbers between the package and the ground. The Package should be covered with tarpaulin immediately after unloading. The area must be well drained to prevent flood damage. Weatherproof coverings which will minimize condensation will be supplied.


Damages

Any evidence of damage must be reported and a claim filed with the carrier. Contact Technibus to initiate corrective action.


Shortages

Verify that all shipping manifest items have been received. Report shortages to the carrier and Technibus immediately. **Failure to report shortages may result in an increased cost which is not the responsibility of Technibus.**

Equipment Handling Illustrations




Fork Lift



24'-0" MAX.

Sling

(SLING BUS SECTION SO WEIGHT IS DISTRIBUTED EQUALLY)



ATTACH LIFTING PROVISIONS TO BUS BARS FOR VERTICAL LIFTS

CLEVIS TYPE LIFTING LUG (LIFTING PROVISIONS BY OTHERS)

NOTE: VERTICAL RUNS MUST BE INSTALLED FROM BOTTOM TO TOP


REMOVE LOWER BRACE AFTER ASSEMBLY IS IN PLACE

Lifting Vertical Sections


Installation / Shipping Fixtures

Drawings	<p>Installation drawings described in the introduction of the manual are essential to identify and assemble the bus system.</p> <p><i>Warning Warning Warning Warning</i> <i>Installation should not be attempted without a complete understanding of the information provided by the drawings.</i></p>
Identification	<p>Each assembly is marked with the corresponding item and shipping split orientation numbers which appear on the Bus Duct Layout drawing(s). Packages containing miscellaneous loose parts required to assemble shipping splits and equipment terminations are identified using this same method.</p>
Lifting Individual Assemblies	<p>Care must be taken to avoid damaging the enclosure and finish when lifting and handling the equipment. Forklifts and slings are most commonly used for this purpose. Typical illustrations are provided on page 9.</p>
Shipping Fixtures	<p>Some assemblies require fixtures to prevent bus movement or damage during handling and installation. Fixtures must be removed after the assembly has been positioned and properly secured.</p>
Contamination	<p>Steps must be taken to avoid entry of dirt and contaminants during installation.</p> <p><u>Prior to testing or operation of system:</u></p> <ul style="list-style-type: none">• Remove all foreign objects and tools from enclosure• Consult Technibus concerning contaminated insulation system• Mask breathers and louvers when applying touch-up paint or using solvents on or near the enclosure• Operate heaters to eliminate moisture from interior components
Assembly	<p>All assemblies should be in place and the bus duct properly positioned at the equipment terminals before housing and conductor hardware are torqued to the proper levels and insulation is applied to the bus bar joints. Note: Bus Duct enclosures are designed based on a 1/4" adjustment gap between side members. This gap may be increased or decreased to accommodate specific site variations.</p>
Modifications	<p>Any alterations or field modifications made to the Technibus bus duct systems which deviate from the installation drawings or this manual require written authorization by Technibus before work is performed. Failure to obtain written approval will result in the voiding of the equipment warranty.</p>


Indoor Non-Vented Enclosure Assembly Illustration



Outdoor Non-Vented Enclosure Assembly Illustration




Wall Entrance Assembly Illustration



Installation Note: Flash and caulk to suit during installation.


Heater System Assembly Illustration - Standard



PART DESCRIPTION

HTR240V/150W (SEE NOTE 2)	WATLOW #SGA1J8A05	FOR ENCL. 10"-27" INSIDE
HTR240V/250W (SEE NOTE 2)	WATLOW #SGA1512A02	FOR ENCL. 27"-51" INSIDE
STD THERMO	THERMODISC 202877	MAX. LOAD 25 AMPERES
		PRESET TO CLOSE @ 95°F & OPEN @ 110°F
OUTDOOR JUNCT BOX	APPLETON JIC-2	
INDOOR JUNCT BOX	1-1/2 X 4 X 4	
WIRE RETAINER	AKRON GASKET 3/16 X 5/8 X 5/8	NEOPRENE
LUGS	PENN UNION YA25-2N	
TERMINAL BLOCK TRW 2-150	NEWARK 29F731	
WIRE	#12 SHIELDED UNLESS OTHERWISE SPECIFIED	

Heater System Assembly Illustration - Hazardous Area



Ground System Assembly Illustration






Illustration A


Hanger and Wall Brace Support Assembly Illustrations




Roof Support - Style I Assembly Illustration




O.A.W.	TYPE	X
13.00	1	12.00
24.00	2	23.00
27.00	3	26.00
30.00	4	29.00
33.00	5	32.00
36.00	6	35.00
42.00	7	41.00
51.00	8	50.00
21.00	9	20.00




Roof Support - Style II Assembly Illustration




O.A.W.	TYPE	X
13.00	1	15.00
24.00	2	26.00
27.00	3	29.00
30.00	4	32.00
33.00	5	35.00
36.00	6	38.00
42.00	7	44.00
51.00	8	53.00
21.00	9	23.00



Single Column Support Assembly Illustration



Double Column Support Assembly Illustration



Bus Joint Assembly / Torque Requirements

Alignment To fully utilize the enclosure and bus alignment provided at each shipping split and equipment connections, do not tighten or insulate connections until the entire system has been installed and properly aligned with equipment terminals.

Contact Surfaces Prior to assembly of a bus joint, inspect contact surfaces for evidence of contamination. When necessary, a mild, non-metallic abrasive (such as Scotch brite), may be required. However, care must be taken to assure that silver plating is not removed during the cleaning process.

Caution Caution Caution Caution

Application of joint compounds or cleaning agents may result in damage to insulating materials and, for this reason, should not be used for cleaning of assembly or bus joints. Refer to the spare parts list for approved insulation and contact cleaning agent.


Typical Bus Joint The illustrations shown on the following pages may not represent actual configurations furnished. Refer to specific details shown on the Bus Duct Layout and Termination drawings provided for hardware and splice plate descriptions.

Copper Bus Joints Copper bus joints will be assembled with split type lock washers. Use the following torque values corresponding to the material furnished. After the hardware has been installed and tightened, re-check torque to assure that loads have been evenly distributed.

Material	Torque in lbs.	Torque in ft. lbs. for each hardware size:			
	5/16	3/8	1/2	5/8	3/4
Grade 5 Plated Steel	215-240	25-30	50-55	65-70	75-80
Stainless Steel	165-180	20-25	40-45	50-55	-
Silicone Bronze	140-150	15-20	30-35	40-45	-


Aluminum Bus Joints Aluminum bus joints are to be tightened to assure that the belleville has been flattened. DO NOT back off after the belleville has reached the flat condition.

Low Voltage Insulating Instructions



Boot Insulation

Insulation boots are secured around the bus joint using serrated push-type non-metallic fasteners. **DO NOT substitute with metallic fasteners or tie-wrap type devices which may contain metallic materials. Boots should be installed to obtain the maximum electrical clearances.**




Boot Insulation

Low Voltage Insulating Instructions

600 - 5000 V Insulating Instructions

1. Apply one (1) half-lapped layer of 1 1/2 inch 3M Brand Scotchfil (or approved equal) over bare conductor and hardware to cover and smooth out the surface. Blend contour into factory insulated surfaces.
2. Wrap joint with (1) half-lapped layer of 1 1/2 inch 3M Brand #130c EPR tape stretching to approximately 2/3 of its original width. Overlap the factory-applied insulation approximately one inch.
3. Wrap one (1) half-lapped layer of 3M Brand #35 jacketing tape over joint completely covering the EPR.




600 - 5000 volt Insulating Illustration

Medium Voltage Insulating Instructions

15kv Insulating Instructions

1. Apply one (1) half-lapped layer of 1 1/2 inch 3M Brand Scotchfil (or approved equal) over bare conductor and hardware to cover and smooth out the surface. Blend contour into factory insulated surfaces.
2. Wrap joint with (2) half-lapped layers of 1 1/2 inch 3M Brand #130c EPR tape stretching to approximately 2/3 of its original width. Overlap the factory-applied insulation approximately two inches.
3. Wrap one (1) half-lapped layer of 3M Brand #35 jacketing tape over joint completely covering the EPR.



15kv Insulating Illustration

Insulating Instructions for 25kv and 38kv


Instructions

1. Fill voids between hardware and corners around splice plates with 3M brand Scotchfil Electrical insulation putty then wrap the bus joint area with the putty. Material should be lightly stretched and half-lapped. This material should stop 3/4" to 1" away from the factory-applied insulation.
2. Apply one (1) continuous half-lapped layer of Scotch 13 (3/4" wide) semi-conductor tape to the entire joint. This tape must contact bus surface and be extended to meet the end of the factory-applied insulation. **Do not overlap insulation. Do not cut tape into short lengths.**
3. Clean surface for insulation in joint area (minimum four (4) inches from the end of insulation) with approved agent.
4. Apply five (5) half-lapped layers of EPR tape with the adhesive side down. Extend first layer 4" onto the factory-applied insulation and taper back toward joint one-half lap with each consecutive layer.

Caution Caution Caution Caution

EPR MUST BE STRETCHED SUFFICIENTLY (ABOUT 2/3 OF WIDTH) TO AVOID ANY FOLDS OR GAPS. Apply enough 3M #130c, 1 1/2" wide EPR tape to the end of the insulation to create a smooth transition from conductor to factory-applied insulation.

5. Apply one (1) half-lapped layer Scotch 35 brown tape completely jacketing the EPR layer. Extend slightly past EPR onto the factory-applied insulation.



38kv Insulating Illustration

Insulating Instructions for 25kv and 38kv

Stud Connector Taping (when required)

1. Apply Scotchfil putty between bolts and over bolts to eliminate sharp edges. Material may be cut into short lengths to build thickness.
2. Apply one (1) continuous half-lapped layer of Scotch 13 semi-conductor tape. This tape is to be brought down onto metal top of porcelain bushings. **Do not cut this tape into short lengths.**
3. Follow steps 4 and 5 on page 27. EPR tape should not extend beyond the top shed of porcelain insulator.


Flexible Connector Taping

1. Follow the Stud Connector Taping steps for areas where flexible connector attaches to the bus bar.
2. Apply five (5) half-lapped layers of EPR tape (adhesive side down) over the entire connection. Extend first layer four (4) inches beyond factory-applied insulation. Each consecutive half-lapped layer should stop short of the preceding layer by one-half lap.

Caution Caution Caution Caution

EPR must be stretched sufficiently (approximately 2/3 of it's original width to avoid any folds or gaps).

3. Cover entire strap and joint area with one (1) half-lapped layer of Scotch 35 Brown tape. Care should be exercised to stretch the tape slightly to avoid folds and gaps.



38kv Flex Connector / Stud Connector Insulating Illustration

Testing

- Bus Installation** Check bus and field applied joint insulation from phase to phase using a 1000 volt megger.
- Control Wiring** Secondary wiring such as heater circuits are subjected to an over-potential test to ground at the factory. A 500 volt megger test is recommended to check field terminal connections.

Power Frequency Withstand

Caution Caution Caution Caution

Insulation and bus supports must be free of contaminants and moisture during testing. Operate heaters prior to testing to assure that moisture is not present. Bus Duct must be disconnected from associated equipment, transformers, potential transformers, etc., prior to withstand test.

In accordance with ANSI C37.23-6.4.2 and tables 3B, 3C, and 3D, a one minute dry power frequency withstand field test can be performed at 75 percent of the factory test levels. Test voltage is applied phase-to-phase and phase-to-ground at the test levels provided in the following tables.

Non-Segregated and *Segregated phase 60Hz System Test Levels

Maximum Operating Voltage kV RMS	Factory Test Level kV RMS	Field Test Levels	
		kV RMS	DC
0.635	2.2	1.65	2.32
4.76	19.0	14.25	20.25
15.00	36.0	27	37.50
15.50 *	50.0 *	37.5 *	52.50 *
25.80	60.0	45	63.75
38.0	80.0	60	-----

*15.5 KV Class test levels are applicable for segregated phase construction only.

DC Test Levels

DC field test levels are provided for reference only for those using DC testing equipment. Values are believed to be appropriate approximate equivalents to the DC levels listed.

DC Bus Duct Systems

Operating Voltage	Factory Test Level (kV RMS)	Field Test Level (DC)
300	2.2	2.32
800	3.7	3.9
1200	4.6	4.9
1600	5.4	5.7

Maintenance

Operation

The entire system must be completely assembled and insulated in accordance with the installation drawing provided.

Caution Caution Caution Caution

Do not attempt to energize incorrectly assembled, damaged or contaminated systems. Prior to operation, damaged components must be repaired and contaminants removed (consult installation section).

Necessary precautions should be taken to avoid using bus duct as a walk way or as a means of support for associated equipment.

Maintenance

Due to possible variations in site conditions, responsibility for establishing a routine maintenance schedule cannot be assumed by Technibus. Top and/or bottom covers are removable for maintenance and inspection. Please check with other manufacturers of equipment used along with the bus duct as well as the work conditions at your site to determine the appropriate maintenance schedule to be followed.

Caution Caution Caution Caution

System must be de-energized to insure personnel safety during inspection and maintenance.

Recommendations

1. A routine inspection to detect deterioration, contamination (see installation section) or damage of all components.
2. Heater circuits and elements should be tested to assure they are operational.
3. Breathers should be cleaned as required.
4. Years of experience have proven that properly assembled conductor connections do not require routine maintenance when operated under normal conditions. **Note: Systems subjected to severe operating conditions which generate excessive localized heating at connections such as periodic overloading or system faults should be checked and re-torqued as required.**

Spare Parts List

Spare Parts

Normal operation will not result in replacement of parts. We recommend miscellaneous items. (i.e. hardware, gasket, or insulation) be available during maintenance activity. A list of common spare parts is provided below. For correct replacement part numbers and pricing, consult Technibus at (330) 478-6395.

The factory will not assume responsibility for the use of substitute replacement parts without it's written authorization. **Substitute replacement parts used without prior written authorization from Technibus will void all warranties.**

Aluminum Extrusions	Cinch Connector TRW 2-150
Access Covers	Junction Box-Indoor
Extrusion Weather Seal	Junction Box-Outdoor
Joiner Cap	Electrical Insulation Putty
Housing Hardware-Indoor/Outdoor	EPR Tape
Enclosure Hardware-Indoor/Outdoor	Jacketing Tape-Red / Brown @ 38kv
Housing Gasket	Shipping Split Boots
Enclosure/Flange Gasket	Termination Boots
Parallelogram Bolts	Boot Hardware
Screened Breather	Expansion Joint Bellows
Fire Stops	Flexible Connectors
Bus Supports-Thru Porcelain	Strain Insulator
Bus Supports-3 Phase	Ground Pads
Porcelain Supports	Stand-off Insulators
Heaters	1/2-13 Concrete Anchors
Thermostat	Power-Strut Hardware Sets
Thermostat-Explosion Proof	
Heater Wire	

For more information regarding Technibus Metal Enclosed Bus Systems and Technibus™ installation and/or maintenance, please call Technibus at (330) 478-6395.

TECHNIBUS

Metal Enclosed Bus Systems

TECHNIBUS
P.O. Box 80777
Canton, Ohio 44708

Telephone: (330) 478-6395
Fax: (330) 478-8377

Bulletin Number 73-394.1